

MYSORE DIVISION.

Notification dated 10th February 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 12 noon on 4th March 1939 for extending the Lakshmanapur Channel, Heggaddevankote Taluk.

2. Tenders in the prescribed form obtainable on payment of Rs. 2 from the Office of the Executive Engineer, Mysore Division, should be addressed to the Executive Engineer, Mysore Division, in a sealed cover and superscribed as "Tender for extending Lakshmanapur Channel, Heggaddevankote Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a deposit of Rs. 500 (in words) Rupees five hundred only credited to the Treasury to 17 (a) P. W. deposits, Promissory Notes or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit in cash will not carry any interest. On acceptance of the tender, the successful tenderer will have to deposit 10% of the value of work.

4. The tenders will be opened in the presence of such tenderers who wish to be present on The final acceptance of the tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the Departmental Schedule Contract form for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Mysore, on all working days between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page, noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions, or additions at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of June 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over

of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(a) The contractor should at his own cost—

- (1) Provide rods, stakes, ropes and labour required in setting out the works.
- (2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
- (3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
- (4) Arrange for protecting work during inclement weather.
- (5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parabs, shoring, strutting and other requisite protective appliances during the progress of the work.
- (6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
- (7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
- (8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
- (9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
- (10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by Insurance at the proper time.

Note.—(b) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Only Chamundi Cement should be used.

Abstract estimate for extending Laxshmanapur Channel Heggaddevankote Taluk.

No.	Items of work	Quantity	Per	Rate	Cost
				Rs. a. p.	Rs.
	<i>Excavation of New Channel.</i>				
1	Earthwork excavating channel and forming bank with spoil in earth	1,223	C.yd.	0 3 6	268
	Do in gravel	2,446	"	0 4 0	612
	Do in gravel with shingle	2,039	"	0 5 6	701
	Do in soft rock	1,631	"	0 8 0	816
	Do in hard rock	815	"	2 0 0	1,630
2	Embankment	220	"	0 5 0	69
3	Turfing, revetment, etc., wherever found necessary		L. S.		290
					4,386
4	Constructing an aquaduct at 3—6 as per separate estimate (details noted in the end)				1,440
5	Constructing a Relieving Waste Weir (4)				
	Earthwork excavation	25	C.yd.	0 4 6	7
	Concrete in surki mortar	86	C.ft.	0 4 6	24
	Burnt brick in surki mortar	225	"	0 5 6	77
	Plastering with surki mortar	25	Sqr.	3 12 0	9
	Rough stone work	24	C.yd.	1 8 0	36
	Earthwork filling and consolidation with watering		L. S.		9
					162
				4 × 162	=648
6	Constructing a pipe sluice (12)				
	Earthwork excavation	2	C.yd.	0 4 6	1
	Concrete in surki mortar	14	C.ft.	0 4 6	4
	Burnt brick in surki mortar	53	"	0 5 6	19
	Plastering with surki mortar	0 75	Sqr.	3 12 0	3
	Cast iron pipe including conveying and fixing	1½	Cwt.	20 0 0	30
	Rough stone revetment	7	C.yd.	1 8 0	11
	Earthwork filling including watering and tamping		L. S.		8
					76
				12 × 76	=912

No.	Items of work	Quantity	Per	Rate	Cost
				Rs. a. p.	Rs.
7.	Constructing a cart bridge—				
	Earthwork excavation for foundation ..	15	Cyd.	0 4 6	4
	Concrete in surki mortar ..	38	C.ft.	0 4 6	11
	Burnt brick in surki mortar ..	315	„	0 5 6	108
	Burnt stone slab 8" to 9" thick ..	65	S.ft.	0 10 0	41
	Coping over parapet including plastering ..	32	R.ft.	0 1 0	2
	Plastering with surki mortar ..	2.68	Sqr.	3 12 0	10
	Rough stone revetment work ..	11	C.yd.	1 8 0	17
	Tarring road way with jelly and gravel and earth-work to approaches ..		L. S.		21
	Total ..				214
8.	Supplying and fixing $\frac{1}{4}$ mile stones ..	9	Each	5 0 0	45
9.	Do bed grade stones ..	36	„	2 8 0	90
	Grand total for excavation of new channel ..				7,735
	<i>Improvements to the Existing Channel.</i>				
1.	Silt and kangoo clearing from bed and slopes of existing channel and forming the bund from the spoil ..	11,648	C.yd.	0 2 6	1,820
2.	Remodelling sluices with necessary repairs and improvements ..	39	Each	15 0 0	585
3.	Repairs to existing masonry walls ..		L. S.		100
4.	Constructing foot bridges in existing channel ..	4	Each	60 0 0	240
	Total ..				2,745
	<i>Details for constructing Aquaduct at 3/6.</i>				
1.	Earthwork excavation in soft rock ..	25	C.yd.	0 8 0	13
	Do gravel ..	125	„	0 4 0	31
2.	Concrete in surki mortar ..	738	C.ft.	0 4 6	208
3.	Burnt brick in surki mortar ..	2,292	„	0 5 6	788
4.	Burnt stone slab 6" thick ..	264	S.ft.	0 10 0	165
5.	Surki mortar plastering ..	27.72	Sqr.	3 12 0	104
6.	Earthwork filling and watering, etc. ..		L. S.		40
7.	Rough stone revetment work ..	47	C.yd.	1 8 0	71
8.	Unforeseen charges such as clearing the ventways so as to have 4 vents of 5'x5' each ..		L. S.		20
	Total ..				1,440
	<i>General.</i>				
1.	Clearing Jungle ..		L. S.		100

D. A. HUKERI,
Executive Engineer.

HASSAN DIVISION.

Abstract Notification dated 31st January 1939.

The attention of the public is invited to the detailed Notification in the *Mysore Gazette*, dated 9th February 1939, vide page Nos. 277-279, Part VI, calling for tenders for restoring Papanaghatta-Naikankere, Channarayaptna Taluk, and the last date for the receipt of tenders is 22nd February 1939.

Abstract Notification dated 4th February 1939.

The attention of the public is invited to the Notification in the *Mysore Gazette*, dated 9th February 1939, vide pages 279-281, Part VI, calling for tenders for constructing a new tank between Ayarahalli and Yagati Villages, Channarayapatna Taluk, and the last date for the receipt of tender is 3rd March 1939.